

CHAINS.	LKS.	
		Hence North bet Sec 28 & 29
47	00	Creek 25 lks wide course East
45	00	Set Post for 1/4 Sec corner bet Sec 28 & 29
90	00	The corner to Sec 20 = 21 = 28 & 29

### Note

Thompson and Chaplain in 1884 in Establishing the line bet Sec 28 & 29 Reports it to be 8000 Chains and W. B. Barr in Surveying the Remainder of this Township in 1881 makes the following Note

East on Random line bet Sec 20 & 29  
Var 21° 10' E

40	00	Set Temporary 1/4 Sec corner
79	70	Intersect N & S line 510 lks South of corner to Sec 20 = 21 = 28 & 29

I Carefully Measure the distance between the Established corners to Sec 28 = 29 = 32 & 33 and Sec 20 = 21 = 28 & 29 and found it to be 8492 Chains I therefore run S 86° 21' W on True line bet Sec 20 & 29.

The 1/4 Sec corner bet Sec 28 & 29  
Hence S 88° W through Sec 29  
Var 20° E

20	00	Set Temporary 1/16 corner
79	50	Intersect 146 lks South of 1/4 Sec corner bet Sec 29 & 30 from which

a Pine 12 inches dia. bet S 4 1/2° W 83 lks dist  
" 20 " " " S 33 1/2° E 107 " "

Hence N 89° 3' E on True line

19	88	Set Post for 1/16 corner in center W 1/2 Sec 29
39	75	The center Sec 29
59	62 1/2	The center E 1/2 Sec 29
79	50	The 1/4 Sec corner bet Sec 28 & 29

The corner to Sec 19 = 20 = 29 & 30

from which  
a Pine 12 inches dia bet N 58° 8' 72 lks dist  
" 10 " " " N 57° W 20 " "  
a Pine 20 " " " S 10° E 108 " "  
" 21 " " " S 25° W 109 " "