

Township 6 South Range 38 East Union County, Oregon.

Hence west bet Sec 19 & 30
 var $20^{\circ} 8'$
 20 50 Set Temporary $\frac{1}{8}$ corner
 40 52 Intersect 152 lks North of $\frac{1}{4}$ Sec corner bet Sec 19 & 30
 from which
 a Pine 24 inches dia. frs $N 45^{\circ} E 25$ lks dist.
 " 9 " " " $S 53^{\circ} W 25$ " "
 Hence $N 87^{\circ} 49' E$ on same line
 20 26 Set Post for $\frac{1}{8}$ corner

 The $\frac{1}{4}$ Sec corner bet Sec 19 & 30
 Hence west bet Sec 19 & 30 var $20^{\circ} 8'$
 20 50 Set Temporary $\frac{1}{8}$ corner
 42 50 Intersect West Boundary 466 lks North of the
 corner to Sec 19 = 30 = 24 & 25 -
 Hence $N 80^{\circ} 47' E$ on same line
 21 25 Set Post for $\frac{1}{8}$ corner
 42 50 The $\frac{1}{4}$ Sec corner bet Sec 19 & 30

 The $\frac{1}{4}$ Sec corner bet Sec 30 & 25 - on Range line
 bet Ranges 37 & 38 East
 Hence East through Sec 30
 20 36 Set Post for center $\frac{1}{4}$ Sec 30
 60 75 Set Post for center $E \frac{1}{2}$ Sec 30
 from which
 a Pine 8 in dia. frs $N 85^{\circ} E 17$ lks dist.
 " 8 " " " $S 78^{\circ} W 14$ " "
 81 15 The $\frac{1}{4}$ Sec corner bet Sec 29 & 30

 The corner of Sec 19 = 20 = 29 & 30
 Hence North bet Sec 19 & 20
 var $21^{\circ} 6'$
 41 41 Intersect 112 lks East of $\frac{1}{4}$ Sec corner bet Sec 19 & 20
 Hence South 48' E on same line
 20 71 Set Post for $\frac{1}{8}$ corner

J. W. Kimbell County Surveyor