

Township

Range

Union County, Oregon.

Thence  $N 89^{\circ} 39' E$  on June line

29.50

Set Post for  $\frac{1}{8}$  corner

40.50

The corner to Sec 19-20-29 & 30

The  $\frac{1}{4}$  Sec corner bet Sec 30 & 25 on Range line  
bet Leases 38 & 39 East

Thence East through Sec 30

60.00

Set Temporary  $\frac{1}{16}$  corner in center  $E \frac{1}{2}$  Sec 30

80.80

Intersect 20  $\frac{1}{2}$  mile north of  $\frac{1}{4}$  Sec corner bet Sec 29 & 30

Thence  $N 89^{\circ} 51 \frac{1}{2}' W$  on June line

The  $\frac{1}{8}$  corner on west boundary  $NE \frac{1}{4}$  Sec 30

Thence South through center  $E \frac{1}{2}$  Sec 30  
to  $12^{\circ} E$

20.00

Set Temporary  $\frac{1}{16}$  corner

40.25

Intersect  $E \frac{1}{2}$  W line 10  $\frac{1}{2}$  miles west of first stake

79.90

Intersect  $\frac{1}{8}$  corner on South boundary  $SE \frac{1}{4}$  Sec 30

Thence North  $var 18^{\circ} 30' E$

39.65

Set Stone 5 + 6 + 24 for  $\frac{1}{16}$  corner in center  $E \frac{1}{2}$  Sec 30

59.77

Set Stone 6 + 8 + 22 for  $\frac{1}{16}$  corner in center  $NE \frac{1}{4}$  Sec 30

John A. Hill County Surveyor