

182
1889

Township 2 South

Range 40 East

Union County, Oregon.

CHAINS.	LKS.	THE CORNER TO LEE 27 = 28 = 33 & 34 Hence West set Lee 28 & 33 FOR 1° 45' E
80 00		Set temporary corner to Lee 28 = 29 = 32 & 33 Hence West set Lee 29 & 33
40 00		found no 1/4 Lee corner Offset 400 lks North
58 50		Set back South 200 lks to Grande Ronde River 200 lks across to left Bank of River to line Hence West on line
54 70		Set temporary 1/4 corner
79 60		found no Lee corner Set temporary corner to Lee 29 = 30 = 31 & 32 Hence West set Lee 30 & 31
81 35		intersected west Boundary at the corner to Lee 30 = 31 = 25 & 36 making an excess of 135 lks in the 3 miles Hence East set Lee 30 & 31
80 45		Set Stake for corner to Lee 29 = 30 = 31 & 32 Hence East
20 02		Set Stone 6x8x20 for 1/4 corner
80 10		The corner to Lee 28 = 29 = 32 & 33 adstone 6x8x16 in line
		<u>The corner to Lee 5 = 6 = 31 & 32</u> <u>Hence North set Lee 31 & 32</u>
40 20		The 1/4 Lee corner set Lee 31 & 32
80 41		The corner to Lee 29 = 30 = 31 & 32 Hence North set Lee 29 & 30
36 34		Grande Ronde River 297 lks across course S.W.
40 20		Set temporary 1/4 Lee corner
80 46		Reset the corner to Lee 19 = 20 = 29 & 30 Hence South
40 2 2		Set Stone 7x6x21 for 1/4 Lee corner set Lee 29 & 30 The 1/4 Lee corner set Lee 31 & 32 Hence East
20 0 3		Set Stone 6x8x12 for 1/4 Lee corner in center W.L. Lee 32
28 0 7		Grande Ronde River 147 lks across course North
40 10		Set Post for center
80 22		intersected East Boundary at 1/4 Lee corner set Lee 32 & 33 Hence West
40 11		Set Stone 8x8x21 for center Lee 32 Hence South through 1/2 Lee 32
40 22		The 1/4 Lee corner set Lee 5 & 32 Hence North
20 11		Set Stone 7x8x12 for 1/4 Lee corner in center S.W. Lee 32
		JO Franklin County Surveyor