

1889

Township 3 South

Range 39 East

Union County, Oregon.

CHAINS. LKS.

Thence South through Sec 8

- 20 07 Set Stake for center N 1/2 Sec 8
- 40 14 The center Sec 8 a Stone 6 x 12 x 18
- 60 22 The center S 1/2 Sec 8
- 80 31 The 1/4 Sec cor bet Sec 8 & 17

The 1/8 corner on South Boundary S W 1/4 Sec 8  
Thence East bet Sec 8 & 17

Var 20° E

- 19 9 1/2 The 1/4 Sec Cor bet Sec 8 & 17  
a Stone 6 x 6 x 22

Thence East

- 39 82 The Corner to Sec 8 = 9 = 16 & 17

Thence West

- 19 9 1/2 Set Stone 4 x 9 x 22 for 1/8 corner

- 39 82 The 1/4 Sec cor bet Sec 8 & 17

The 1/8 Corner on West Boundary N W 1/4 Sec 8  
Thence East through N 1/2 Sec 8

Var 20° E

- 20 00 Set Temporary 1/16 corner
- 40 20 Intersect N & S line 5 lks South of center N 1/2
- 52 20 Set Temporary Fractional Corner bet Oliver & Stone
- 60 20 Set Temporary 1/16 corner
- 80 46 The 1/8 corner on East Boundary N E 1/4 Sec 8  
Thence West through N 1/2 Sec 8

- 20 13 Set Stone 8 x 12 x 28 for 1/16 cor in Center N E 1/4 Sec 8
- 28 19 Set Stone 7 x 7 x 25 for Fractional Corner bet Oliver & Stone
- 40 26 The center N 1/2 Sec 8 a Stone 8 x 10 x 15
- 60 39 Set Stone 6 x 12 x 20 for 1/16 cor in Center N W 1/4 Sec 8
- 80 46 The 1/8 corner on W Bdy N W 1/4 Sec 8

The center E 1/2 Sec 8 Thence North

- 40 15 The 1/8 corner on South Bdy S E 1/4 Sec 8 Thence North

- 20 07 1/2 Set Stone 5 x 6 x 22 for 1/16 cor in Center S E 1/4 Sec 8

The 1/8 corner on South Boundary S W 1/4 Sec 8 Thence North

- 40 17 The center W 1/2 Sec 8 Thence South

- 20 08 1/2 Set Stone 6 x 12 x 20 for 1/16 corner in Center S W 1/4 Sec 8