

Township 7 North & 1 South

Range 39 East

Union County, Oregon.

CHAINS.	LKS.	
		The Corner to Sec 3=4=33 & 34 Thence North bet Sec 33 & 34
40	96	The 1/4 Sec corner bet Sec 33 & 34 Thence South
20	48	Set 1/8 corner
40	96	The line to Sec 3=4=33 & 34
		The corner to Sec 2=3=34 & 35 - on Base Line Thence North bet Sec 34 & 35 -
40	62	The 1/4 Sec corner bet Sec 34 & 35 - Thence South
20	31	Set Stone 6 x 16 x 44 in mound of Stone for 1/8 corner Thence West through S 1/2 Sec 34 Cor 20° E
29	88	Top of Rocky Bluff East of Grand Round River
31	92	Right Bank of Grand Round River
34	46	Left Bank of Grand Round River
40	00	Set Temporary center S 1/2 Sec 34
60	00	Set Temporary 1/16 corner
80	96	The 1/8 corner on west boundary S W 1/4 Sec 34 Thence East through center South 1/2 Sec 34
20	23	Set Post in mound of Stone for 1/16 corner in center S W 1/4
40	46	Set Stone in mound of Stone for center S 1/2 Sec 34
		The corner to Sec 1=2=35 & 36 on Base Line Thence West bet Sec 2 & 35 - Cor 21° E
20	00	Set Temporary 1/8 corner
40	00	Set Temporary 1/4 Sec corner
80	36	The corner to Sec 2=3=34 & 35 - Thence East bet Sec 2 & 35 -
40	18	Set Stone 8 x 16 x 19 for 1/4 Sec Cor bet Sec 2 & 35 -
60	27	Set Post in mound of Stone for 1/8 corner
80	36	The corner to Sec 1=2=35 & 36 Post decayed Set Stone 6 x 9 x 25 for corner to Sec 1=2=35 & 36 Thence South bet Sec 1 & 2 Cor 19° 45' E
20	00	Set Temporary 1/8 corner
80	75	The corner to Sec 1=2=11 & 12