

CHAINS  
Lks.

The 1/4 Sec corner bet Sec 4 & 5  
Thence East through Sec 4  
Var 20° E

- 20 00 Set Temporary 1/16 corner
- 70 53 Set Temporary center Sec 4
- 50 20 Intersect 30 lks South of the 1/4 Sec cor bet Sec 3 & 4  
Thence S 89° 47' W on True line
- 20 17 Set Post in Mound of Stone for 1/16 cor in Center E 1/2 Sec 4
- 40 07 The center Sec 4
- 60 01 The center W 1/2 Sec 4
- 80 20 The 1/4 Sec cor bet Sec 4 & 5

The 1/4 Sec cor bet Sec 4 & 33 on Base Line  
Thence S 2° E through Sec 4  
Var 20° E

- 33 34 Top of Berkeley Bluff Telescope measurement 638 lks to flag
- 39 81 Intersect E & W line 5 lks East of first stake at center
- 79 98 Intersect 22 lks East of the 1/4 Sec corner bet Sec 4 & 9

The 1/8 corner on South Boundary S W 1/4 Sec 4  
Thence North 2° W through Center W 1/2 Sec 4

- 40 10 Intersect E & W line 9 1/2 lks East of first stake.
- 60 10 Set Temporary 1/16 corner
- 79 60 Intersect North Boundary at 1/8 cor  
Thence South 2° E

- 19 47 Set Stone 7 x 11 x 25 for 1/16 cor in Center NW 1/4 Sec 4
- 39 50 Set Stone 3 x 7 x 36 for 1/16 cor in Center W 1/2 Sec 4

The corner to Sec 5 = 6 = 7 & 8  
Thence West bet Sec 6 & 7  
Var 20° E

- 40 00 Set Temporary 1/4 Sec corner
- 79 10 Intersect West Boundary 18 lks South of corner to Sec 6 = 7 = 8  
Thence S 89° 55' E on True line bet Sec 6 & 7
- 38 60 Set Stone 4 x 16 x 22 for 1/4 Sec corner bet Sec 6 & 7
- 79 10 The corner to Sec 5 = 6 = 7 & 8

J. W. Merrill County Surveyor