

CHAINS.	LKS.	
		Hence North $11^{\circ} E$ Through Center Sec 7 Var $20^{\circ} E$
40	05	Set Post for center Sec 7
60	07 1/2	Set Stone $6 \times 7 \times 32$ for $1/4$ corner in center N 1/2 Sec 7
80	10	The $1/4$ Sec corner bet Sec 6 & 7
		The $1/4$ Sec corner bet Sec 17 & 18 Hence North bet Sec 17 & 18 Var $20^{\circ} E$
40	07	The corner to Sec 7 = 8 = 17 & 18 Hence North bet Sec 7 & 8 Var $20^{\circ} E$
40	00	Set Temporary $1/4$ Sec corner
80	12	The corner to Sec 5 = 6 = 7 & 8 Hence South
14	97	Center of Willow Creek course East Set Stone $10 \times 10 \times 25$ on North or Left Bank of Willow Creek 25 lks North of True $1/4$ corner which is in the center of Willow Creek
40	06	Set Stone $5 \times 14 \times 23$ for $1/4$ Sec corner
80	12	The corner to Sec 7 = 8 = 17 & 18
		The $1/4$ Sec corner bet Sec 8 & 9 Hence West Through Sec 8 Var $20^{\circ} E$
40	00	Set Temporary Center Sec 8
80	42	Intersect 17 lks North of $1/4$ Sec cor bet Sec 7 & 8 Hence $N 89^{\circ} 58' W$ on True line Through Sec 8
40	46	Set Stone $5 \times 8 \times 15$ for center Sec 8
80	92	The $1/4$ Sec cor bet Sec 8 & 9
		The $1/4$ Sec corner bet Sec 8 & 17 Hence North Through Sec 8 Var $20^{\circ} 30' E$
40	13	Intersect E & W line
69	12	Bluff on South Side of Willow Creek
80	23	The $1/4$ Sec cor bet Sec 5 & 8
		The corner to Sec 16 = 17 = 20 & 21 Hence East bet Sec 16 & 21 Var $20^{\circ} E$