

RECORD OF SURVEY

207
1889

Township 7 South

Range 45 East

Union County, Oregon.

CHS. LRS. The corner to Sec. 24=25=19 & 30 on Range line
Thence west bet Sec 24 & 25 -
var 20° E

20 00 Set Temporary 1/8 corner
40 54 Intersect 15 lks south of the 1/4 Sec corner bet Sec 24 & 25 -
Thence S 89° 47' E on true line

20 27 Set Stone 6 x 11 x 18 for 1/8 corner
Thence south through NE 1/4 Sec 25 -
var 20° E

20 00 Set Temporary 1/16 corner
40 29 The 1/16 corner in Center E 1/2 Sec 25 -
Thence north through center NE 1/4

20 14 1/2 Set Stone 8 x 10 x 18 for 1/16 corner in Center NE 1/4 Sec 25 -
40 29 The 1/8 corner on North Side NE 1/4 Sec 25 -

The Center S 1/2 Sec 25 -
Thence west through SW 1/4 Sec 25 -
var 20° E

5 00 Creek course S E
13 50 " " S E

20 50 Set Temporary 1/16 corner
40 54 Intersect 42 lks North of 1/8 corner on W Boundary SW 1/4
Thence N 89° 24' E on true line
Through the center of the SW 1/4 Sec 25 -

20 02 Set Stone 9 x 15 x 22 inches for 1/16 cor in center SW 1/4
from which
an asp 6 inches dia. to S 69° W 33 lks dist -
" 5 " " " N 47 1/2° E 25 " "

40 54 The 1/16 corner in center S 1/2 Sec 25 -

The corner to Sec 25=26=35 & 36
from which
a pine 5 inch dia. to N 57° E 46 lks dist.
" 48 " " " N 89° W 302 " "
" 40 " " " S 87° W 300 " "
" 46 " " " S 20° E 10 " "
Thence north bet Sec 25 & 26

19 95 The 1/8 corner
39 90 The 1/4 Sec corner bet Sec 25 & 26