

The 1/4 Sec corner bet Sec 31 & 36
from which
a cottonwood 5 inch dia. brs N 29° E 27 lks dist.
" 6 " " " S 55° W 45 " "
thence East through Sec 31
Var 20° E

19 40 Set Temporary 1/16 cor
38 70 Intersect Line N W 1/4 Sec 4 lks North of center

58 70 Set Temporary 1/16 corner
78 64 Intersect 8 lks North of 1/4 Sec corner bet Sec 31 & 32
from which

an alder 6 inch dia brs N 9° E 33 lks dist.
a Pine 60 " " " S 75° W 4 " "
Thence N 89° 57 1/2 W on line

19 97 Set Stone 9 x 9 x 20 for 1/16 cor in center 8 1/2 Sec 31
from which
a Pine 4 inch dia. brs N 5 1/2° W 17 lks
" 4 " " " S 59° E 31 "

39 94 The center Sec 31 a Stone 10 x 11 x 20 inches

59 77 Set Stone 10 x 10 x 19 for 1/16 cor in center W 1/2 Sec 30
from which
a Pine 6 inches dia. brs S 89° 30' W 364 lks dist.

78 64 The 1/4 Sec corner bet Sec 31 & 36

The 1/4 Sec corner bet Sec 31 & 32
thence South bet Sec 31 & 32
Var 20° E

40 21 Intersect 94 lks west of corner to Sec 5 = 6 = 31 & 32
from which
a Pine 24 in dia brs N 9 1/2° E 492 lks distant

The 1/8 corner on South Boundary S E 1/4 Sec 31
thence North through S E 1/4 Sec 31
Var 20° E

40 31 The 1/16 cor in center 8 1/2 Sec 31
thence South through center S E 1/4

20 15 1/2 Set Stone 8 x 9 x 18 for 1/16 cor in center S E 1/4 Sec 31

The 1/8 corner on North Boundary N W 1/4 Sec 31
thence South through N W 1/4
Var 20° E

40 47 The 1/16 corner in center W 1/2 Sec 31
thence North through N W 1/4

20 23 1/2 Set Stone 9 x 12 x 26 in corner of Stone in center N W 1/4 Sec 31

J. W. Kimbrell County Surveyor