

CHAINS	LINKS	
		The corner to Sec 25 = 26 = 35 & 36 Thence East bet Sec 25 & 36 Var 20° 45' E
20 00		Set Temporary 1/8 corner
40 00		Set Temporary 1/4 Sec corner
79 00		Intersect 28 lks South of corner to Sec 30 = 31 = 25 & 36 Thence S 89° 48' W on true line bet Sec 25 & 36
39 50		Set Post in Mound of Stone in Old bet of creek for 1/4 Sec cor bet Sec 25 & 36
59 25		Set Post for 1/8 corner from which a cottonwood 12 inch dia. frs S 2 1/2° W 302 lks dist a willow 4 " " " N 46° E 108 " "
79 00		The corner to Sec 25 = 26 = 35 & 36 The 1/4 Sec corner bet Sec 25 & 36 Thence North through Sec 25 - Var 20° E
4 00		Plough 100 lks across course East
14 00		Powder River 408 lks across course S 15° E
20 00		Set Temporary 1/16 corners
36 25		Spring Branch 25 lks. across course East
40 00		Set Temporary center Sec 25 -
60 00		Set Temporary 1/16 corner
80 12		Intersect 105 lks East of 1/4 bet Sec 24 & 25 - Thence S 45° E on true line
20 03		Set Post for 1/16 corner in center N 1/2 Sec 25 -
40 06		Set Post for center Sec 25 -
60 09		Set Post for 1/16 corner in center S 1/2 Sec 25 - from which a cottonwood 3 inch dia. frs South 6 lks dist
80 12		The 1/4 Sec cor bet Sec 25 & 36 The 1/4 Sec corner bet Sec 25 & 26 Thence East through Sec 25 - Var 20° E
19 8 1/2		Set Temporary 1/16 corner
39 75		Intersect N & S Line 4 lks North of center state
59 62 1/2		Set Temporary 1/16 corner
77 75		Powder River 168 lks across course N 15° E
79 55		Intersect 5 lks North of 1/4 Sec cor bet Sec 30 & 25 - from which a cottonwood 1 1/2 inch dia. frs S 80° E 60 lks dist