

CHISEL LRS.  
 22 Powder River  
 19 90 Set Post for  $\frac{1}{16}$  corner in Center E  $\frac{1}{2}$  Sec 25-  
 from which  
 a cottonwood 7 inches dia. bcs  $S 10^{\circ} W$  16 lks dist.  
 39 80 The center Sec 25-  
 59 67 Set Stone 8 x 9 x 14 for  $\frac{1}{16}$  corner in Center W  $\frac{1}{2}$  Sec 25-  
 79 55 The  $\frac{1}{4}$  Sec cor bet Sec 25 & 26

The  $\frac{1}{16}$  corner in Center N  $\frac{1}{2}$  Sec 25-  
 Thence West through N W  $\frac{1}{4}$  Sec 25-

20 00 Set Temporary  $\frac{1}{16}$  cor  
 39 85 The  $\frac{1}{8}$  corner on West Boundary N W  $\frac{1}{4}$  Sec 25-  
 Thence East through center N W  $\frac{1}{4}$   
 19 82  $\frac{1}{2}$  Set Post for  $\frac{1}{16}$  corner in center N W  $\frac{1}{4}$  Sec 25-

from which  
 a cottonwood 4 inches dia bcs  $N 88^{\circ} E$  91 lks dist.  
 " " 4 " " " South 41 " "

39 85 The center N  $\frac{1}{2}$  Sec 25-

The corner to Sec 25-26-35 & 36  
 Thence West bet Sec 26 & 35  
 var  $20^{\circ} 30' E$

2 40 Powder River 283 lks across course  $N 80^{\circ} E$   
 10 75 through 30 lks across course South

20 00 Set Temporary  $\frac{1}{8}$  corner  
 36 75 Eagle Creek 75 lks across course  $S 25^{\circ} E$   
 40 26 Intersect 9 lks South of  $\frac{1}{4}$  Sec corner bet Sec 26 & 35-

from which  
 a Cottonwood 8 inch dia bcs  $N 11^{\circ} W$  26 lks dist.  
 " 8 " " "  $S 26^{\circ} W$  30 " "

Thence  $S 89^{\circ} 52' E$  on true line bet Sec 26 & 35-

20 13 Set Post for  $\frac{1}{8}$  corner  
 from which  
 a Cottonwood 6 inch dia. bcs  $N 71^{\circ} E$  205 lks dist.  
 an alder 2 " " "  $S 48^{\circ} W$  33 " "

40 26 The corner to Sec 25-26-35 & 36

The  $\frac{1}{4}$  Sec corner bet Sec 25 & 26  
 Thence West through Sec 26  
 var  $20^{\circ} E$