

CHAINS  
LKS.

The corner to Sec 23=24=25 & 26

Thence West bet Sec 23 & 26

Var 20° E

20 50 Set Temporary 1/8 corner

40 20 Intersect 22 lks North of the 1/4 Sec corner bet Sec 23 & 26

Thence N 84° 38' E on True Line bet Sec 23 & 26

40 10 Set Stone 6 x 8 x 20 for 1/8 corner

40 20 Thence to Sec 23=24=25 & 26

The 1/4 Sec corner bet Sec 23 & 26

Thence West bet Sec 23 & 26

Var 20° E

19 00 Left Bank of Eagle creek Course S 10° E

20 00 Set Temporary 1/8 corner

20 75 Right Bank of Eagle creek Course S 10° E

38 87 Intersect 84 lks South of corner to Sec 22=23=26 & 27

Thence S 88° 48' E on True line bet Sec 23 & 26

19 43 Set Post in Bed of Eagle creek

Thence South through W 1/4 Sec 26

Var 20° E

223 Right-Bank of Eagle creek Course S 35° E

20 00 Set Temporary 1/6 corner

40 12 Intersect 56 lks West of 1/6 corner in center W 1/4 Sec 26

Thence N 48' W on True line through center N W 1/4

20 06 Set Post for 1/6 corner in Slough for center N W 1/4 Sec 26

from which

a Cottonwood 15 inches dia bet N 71° E 56 lks dist

" " 17 " " " N 22 1/2° W 101 " "

The 1/6 corner in center E 1/4 Sec 26

Thence South through S E 1/4 Sec 26

Var 20° E

20 00 Set Temporary 1/6 corner

40 21 Intersect 79 lks West of 1/6 corner on South Boundary S E 1/4

Thence N 1° 8' W on True line through S E 1/4

20 10 1/2 Set Stone 6 x 8 x 16 for 1/6 corner in center S E 1/4 Sec 26

from which

a cottonwood 3 inch dia bet S 11 1/2° W 108 1/2 lks dist

J. W. Kimbrell County Surveyor

27