

Township 5 South Range 40 East Union County, Oregon.

The 1/4 Sec corner bet Sec 7 & 8  
 Thence West through Sec 7  
 Var 20° E

20 50 Set Temporary 1/16 corner  
 40 50 Set Temporary center Sec 7  
 71 53 Rail Road course S E & N W  
 80 84 1/2 intersect - 14 lks South of 1/4 Sec corner bet Sec. 7 & 12  
 Thence S 89° 54' E on True line through Sec 7  
 40 57 center Sec 7  
 60 70 Set Stone 6 x 10 x 25 in Mound of Stone for 1/16 cor in center E 1/2 Sec 7  
 80 84 The 1/4 Sec corner bet Sec 7 & 8 -

The 1/4 Sec corner bet Sec 7 & 12  
 Thence North through Sec 7  
 Var 20° E

20 50 Set Temporary 1/16 corner  
 40 07 Intersect True E & W line 5 lks East of Center  
 80 50 Intersect 10 lks East of 1/4 Sec corner bet Sec 6 & 7  
 Thence South  
 40 43 The Center Sec 7  
 60 46 1/2 Set Stone 3 x 4 x 18 for 1/16 corner in Center S 1/2 Sec 7  
 80 50 The 1/4 Sec corner bet Sec 7 & 18

The 1/4 Sec corner bet Sec 7 & 12 on Guide Meridian  
 Thence South bet Sec 7 & 12

40 58 The corner to Sec 7 = 12 = 12 & 13  
 Thence North

20 29 Set Stone in Mound of Stone for 1/4 corner  
 Thence East through S 1/2 Sec 7

19 50 Rail Road S E & N W  
 40 33 center S 1/2 Sec 7  
 The 1/16 corner in Center E 1/2 Sec 7 Thence North Var 20° E

39 93 The 1/2 corner on South boundary S E 1/4 Sec 7  
 Thence North

19 96 Set Stone 5 x 10 x 18 for 1/16 corner in Center S E 1/4 Sec 7  
 Thence North 94 3/4 Rods Set Stone 7 x 10 x 32 in Mound of Stone  
 Thence S 55° W 166 1/4 Rods Set Stone 7 x 10 x 23 for fractional corner  
 Thence East 136 Rods to Place of Beginning the Center S E 1/4

J. W. Kimball County Surveyor