

CHAINS.	LINKS.	
		The 1/4 Sec corner bet Sec 3 & 10 Thence North through Sec 3 Var 20° E
12	50	Descend steep Hill side
18	00	foot of Hill
20	00	Set Temporary 1/16 corner
23	00	Wolf creek runs East
35	00	Clear creek Course S E
40	00	Set Temporary Center Sec 3
77	39	Intersect - 30.2 lks East of 1/4 Sec corner bet Sec 3 & 34 Thence S 2° 10' E on true line through Sec 3
		The 1/4 Sec corner bet Sec 3 & 4 Thence East through Sec 3 Var 20° E
36	50	Clear creek Course S E
39	24	Intersect - True N & S line 23 lks South of first Stake at center
82	34	Intersect - 195 lks North of 1/4 Sec corner bet Sec 2 & 3 Thence N 88° 24' W on true line through Sec 3
43	10	Set Post for center in mound of Stone from which a Sawrack 12 inches dia by N 18 1/2° W 75 lks dist Thence South through S 1/2 Sec 3
19	42 1/2	Set Post for 1/16 corner in center S 1/2 Sec 3 Thence west through S W 1/4 Sec 3 Var 20° E
20	00	Set Temporary 1/16 corner
40	06	Intersect 43 lks South of 1/8 corner on W by S W 1/4 Sec 3 Thence S 88° 40' E on true line through S W 1/4
20	03	Set Post for 1/16 corner in center S W 1/4 Sec 3 from which a fir 5 inch dia tree S 76° W 65 lks dist
		The 1/4 Sec corner bet Sec 3 & 4 Thence west through Sec 4 Var 20° E
20	00	Set Temporary 1/16 corner
26	00	Wolf creek runs S E
28	00	Shingle Patch runs N E
40	00	Set Temporary center
82	00	Intersect 100 lks South of 1/4 Sec corner bet Sec 4 & 5 Thence S 89° 17' E on true line through Sec 3