

Township 2 South

Range 37 East

Union County, Oregon.

CHAINS.

LKS.

- The corner to Sec 2-3-34 & 35 on T<sub>10</sub> line,  
bet Townships 2 & 3 South  
which is a Post in mound of Stone  
Thence East on T<sub>10</sub> line  
bet Sec 2 & 35-
- 22 30 Set Post in mound of Stone for  $\frac{1}{8}$  corner  
from which  
a Pine 24 in dia N41° E 22 lks dist  
" 22 " " S61° W 48 " "
- 44 60 The  $\frac{1}{4}$  Sec corner bet Sec 2 & 35-
- The  $\frac{1}{8}$  corner on South Boundary of NW  $\frac{1}{4}$  Sec 35-  
thence North 1° 48' W  
var 15° E
- 23 48 Top of Rock Bluff  
ascend
- 5 30 var 22° E
- 17 00 var 17° 30' E
- 15 00 var 22° 30' E
- 21 50 Grande Round 230 lks across course N 80° E  
var 22° E
- 30 48 Top of Ridge
- 31 75 Rail Road E & W
- 33 00 through 410 lks across
- 40 00 Set Temporary center W  $\frac{1}{2}$  Sec 35-
- 73 00 ascend steep South Hillside.
- 81 00 Intersect  $\frac{1}{8}$  corner on North Boundary NW  $\frac{1}{4}$  Sec 35-  
thence South through NW  $\frac{1}{4}$  Sec 35-
- 40 50 center W  $\frac{1}{2}$  Sec 35-  
thence West through W  $\frac{1}{2}$  NW  $\frac{1}{4}$  Sec 35-
- 21 00 The  $\frac{1}{4}$  Sec corner bet Sec 34 & 35 -  
from which  
a Pine 12 inch S63° E 32 lks dist  
fir 5 " North 30 " "

J. W. Kimbrell