

Township

Range

Union County, Oregon.

- 28 28 Left Bank of Catherine Creek Course $N 85^{\circ} W$
 35 45 a Stone marked 14 but not set firmly in the ground
 and from all appearances has been moved from its original position
 and as there is such a difference in the distance between it and the
 corner to Sec 2-3-34 & 35 and bet it and Catherine Creek
 as per U S Field Notes that I proceed on west
 to test the correctness of its position
- 40 00 Set Temporary $\frac{1}{4}$ Sec Corner
 79 67 Intersect 26 lbs North of Corner of Sec 3-4-33 & 34
 Thence $N 89^{\circ} 49'$ E on same line
 Var $20^{\circ} 45' E$
- 39 83 Set Stake for $\frac{1}{4}$ Sec Corner of Sec 3 & 34
 Thence North through Sec 34
- 19 00 Catherine Creek Course N.W.
 20 00 Right Bank of Catherine Creek
 Thence East through Sect $E \frac{1}{2}$ Sec 34
- 39 02 Intersect 20 lbs North of $\frac{1}{8}$ corner on E Boundary of $E \frac{1}{4}$ Sec 34
 Thence $N 89^{\circ} 48'$ west on same line
- 19 51 Set Post in mound of Stone for $\frac{1}{16}$ corner in Center $S W \frac{1}{4}$ Sec 34

J W Kimball County Surveyor