

Township 5 South

Range 40 East

Union County, Oregon.

CHAINS  
FMS.

from which  
a Pine 20 inches dia. bes  $S 49^{\circ} W 52$  lks dist.  
" 20 " " " "  $N 26^{\circ} W 57$  " "  
The corner to Sec 1-2-11-12

The  $\frac{1}{4}$  Sec corner bet Sec 11 & 12  
Thence west through Sec 11  
Var  $20^{\circ} E$

40 00 Set Temporary center Sec 11

80 15 Intersect - 147 lks South of  $\frac{1}{4}$  Sec corner bet Sec 10 & 11  
Thence  $S 88^{\circ} 57' E$  on June line through Sec 11

The  $\frac{1}{4}$  Sec corner bet Sec 2 & 11  
Thence South through Sec 11  
Var  $20^{\circ} 30' E$

20 00 Set Temporary  $\frac{1}{16}$  corner

39 55 Intersect - June E & W line 51 lks East of 1<sup>st</sup> Stake at center

80 83 Intersect - 14 lks west of the  $\frac{1}{4}$  Sec corner bet Sec 11 & 14  
Thence  $N 6^{\circ} W$  through Sec 11

41 28 The center Sec 11

61 07 Set Stone  $12 \times 12 \times 24$  for  $\frac{1}{16}$  corner in center  $N \frac{1}{2}$  Sec 11  
Thence East through  $N \frac{1}{4}$  Sec 11

39 87 Intersect - 36 lks North of  $\frac{1}{8}$  corner on East bdy  $N \frac{1}{4}$  Sec 11

Thence  $N 89^{\circ} 29' W$  on June line  
through center  $N \frac{1}{4}$  Sec 11

37 84 The  $\frac{1}{16}$  corner in center  $N \frac{1}{2}$  Sec 11

Submittal County Surveys