

Township 7 North

Range 40 East

Union County, Oregon.

CHAINS	LINKS	
		Thence S 89° 36' E on true line through Sec 30
17	40	Set Post for $\frac{1}{16}$ corner in center W $\frac{1}{2}$ Sec 30 ^{from which} a Hawthorn 4 in dia S 2° W 12 lbs dist
37	14	Set stone 9 + 17 + 34 in mound of stone for center Sec 30
		Thence South through S $\frac{1}{4}$ Sec 30
19	57	The $\frac{1}{16}$ corner in center of S $\frac{1}{4}$ Sec 30 in center of Clark's creek from which
		an alder 6 inch dia bes N 1½° W 15 lbs dist
		" 4 " " " N 17° E 18 " "
39	15	The $\frac{1}{4}$ Sec corner bet Sec 30 & 31
		The corner to Sec 30 = 31 = 25 & 36
		Thence East - bet Sec 30 & 31
19	72	Set Temporary $\frac{1}{8}$ corner var 2½° E
33	12	Intersect $\frac{1}{4}$ Sec corner bet Sec 30 & 31
		Thence west - bet Sec 30 & 31
16	70	Set Post for $\frac{1}{8}$ corner
		Thence North through W $\frac{1}{2}$ Sec 30
20	00	Set Temporary $\frac{1}{16}$ corner
39	62	The center W $\frac{1}{2}$ Sec 30 a Post
		from which
		a Hawthorn 4 inch dia bes S 2° W 12 lbs dist
		Thence North through N W $\frac{1}{4}$ Sec 30
20	00	Set Temporary $\frac{1}{16}$ corner
41	00	The $\frac{1}{8}$ corner on North boundary N W $\frac{1}{4}$ Sec 30
		Thence South through N W $\frac{1}{4}$
20	50	Set Stone 5 + 13 + 24 for $\frac{1}{16}$ corner in center N W $\frac{1}{4}$
41	00	center West $\frac{1}{2}$ Sec 30

J. W. Kimbrell County Surveyor