

Township 4 N 5 South

Range 39 East

Union County, Oregon.

CHAINS. LKS.

The 1/4 Sec corner bet Sec 2 & 3

Hence East through Sec 2

Var 20° 7' E.

40 00 Set Temporary center Sec 2 on top of Ridge NW 1/4 S E

60 00 Set Temporary 1/16 corner

71 28 Intersect 85 lks South of 1/4 Sec corner bet Sec 1 & 2

Hence S 89° 23' W on same line through Sec 2

The 1/4 Sec corner bet Sec 2 & 35-

Hence South through Sec 2

Var 20° E

20 00 Set Temporary 1/16 corner

39 85 Intersect True E & W line 85 lks West of 1st Stake at center

59 85 Set Temporary 1/16 corner

80 22 Intersect 293 lks West of the 1/4 Sec corner bet Sec 2 & 31

Hence N 2° 6' W on same line through Sec 2

20 13 1/2 Set Stone in mound of Stone for 1/16 corner in center S 1/2 Sec 2

40 27 Set Stone in mound of Stone for center Sec 2 on top of Ridge S 25° E N 25° W

60 27 Set Stone in mound of Stone for 1/16 corner in center N 1/2 Sec 2

80 22 The 1/4 Sec corner bet Sec 2 & 35 -

The center Sec 2 Hence East

20 33 1/2 Set Post in mound of Stone for 1/16 corner in center E 1/2 Sec 2

40 67 The 1/4 Sec corner bet Sec 1 & 2

Hence South bet Sec 1 & 2

Var 20° E

20 00 Set Temporary 1/8 corner

40 45 Intersect the corner of Sec 1 = 2 = 11 1/2

Hence North bet Sec 1 & 2

20 22 1/2 Set Stone in mound of Stone for 1/8 corner

40 45 The 1/4 Sec corner bet Sec 1 & 2

The corner of Sec 1 = 2 = 11 1/2

Hence South bet Sec 11 1/2

Var 20° E

20 00 Set Temporary 1/8 corner

40 20 Intersect 50 lks West of 1/4 Sec corner bet Sec 11 1/2

Hence N 43° W on same line bet Sec 11 1/2

20 10 Set Stone in mound of Stone for 1/8 corner

40 20 The corner of Sec 1 = 2 = 11 1/2

Hence East bet Sec 1 & 2 Var 20° E

20 00 Set Stone in mound of Stone