

Township 4 & 5 South Range 39 East Union County, Oregon.

CHAINS.	LINKS.	
		The corner to Sec 2=3=34 & 35 - Thence East on Tp line to Sec 1 & 34 Var 20° E
20	00	Set Temporary 1/8 corner
40	24	Intersect 24 lks North of 1/4 Sec corner to Sec 2 & 35 - Thence N 89° 38' W on Town line
20	12	Set Stone in Mound of Stone for 1/8 corner
40	24	The corner to Sec 2=3=34 & 35 -
		The 1/8 corner on West Boundary N W 1/4 Sec 2 Thence East through N W 1/4 Sec 2 Var 20° E
20	00	Set Temporary 1/16 corner
40	44	Intersect 1/16 corner in center N 1/2 Sec 2 Thence West through N W 1/4
20	22	Set Post for 1/16 corners in center N W 1/4 Sec 2
		The 1/4 Sec corner to Sec 2 & 11 Thence East to Sec 2 & 11 Var 20° 30' E
20	00	Set Temporary 1/8 corner
37	50	Intersect corner to Sec 1=2=11 & 12 Thence West to Sec 2 & 11
18	75	Set Stone in Mound of Stone for 1/8 corner
37	50	The 1/4 Sec corner to Sec 2 & 11
		The corner to Sec 2=3=34 & 35 - Thence North to Sec 34 & 35 - Var 20° E
20	00	Set Temporary 1/8 corner
41	05	Intersect 105 lks West of 1/4 Sec corner to Sec 34 & 35 - Thence S 1° 30' W on Town line
20	52 1/2	Set Stone in Mound of Stone for 1/8 corner
41	05	The corner to Sec 2=3=34 & 35 -
		The 1/8 corner on South Boundary S W 1/4 Sec 35 - Thence North through S W 1/4 Sec 35 -
20	00	Set Stone in Mound of Stone for center S W 1/4 Thence West through W 1/2 S W 1/4
20	00	The 1/8 corner on West Boundary S E 1/4 Sec 35 -