

Township 2 South Range 40 East Union County, Oregon.

The 1/4 Sec corner bet Sec 5 & 8

Thence North through Sec 5 -  
var 20° E

20 00 Set Temporary 1/16 corner

34 45 Intersect True E of W. Line 17 lks west of 1st Stake at center

59 45 Set Temporary 1/16 corner

80 22 Intersect 1/4 Sec corner bet Sec 5 & 32

Thence South through Sec 5 -

19 34 Set Post in Mound of Stone for 1/16 corner in center N 1/2 Sec 5 -  
from which

a Pine 8 inch dia bet N 87° W 28 lks dist

40 77 Set Post for center Sec 5

from which

a Pine 3 inch dia bet S 61° E 12 1/2 lks dist

60 50 Set Post for 1/16 corner in center S 1/2 Sec 5 -

from which

a Pine 3 inch dia bet N 55° W 17 lks dist

80 22 The 1/4 Sec corner bet Sec 5 & 8 -

The 1/4 Sec corner bet Sec 5 & 6

Thence South bet Sec 5 & 6

var 20° E

20 00 Set Temporary 1/8 corner

34 78 Intersect 78 lks East of Corner of Sec 5 = 6 = 7 & 8

from which

a Sawnack 12 inch dia bet S 48° E 25 lks dist

" 12 " " " S 22° W 6 " "

" 14 " " " N 68° W 48 " "

a Pine 12 " " " N 40° E 61 " "

Thence North 1° 7' E on True line

19 89 Set Post for 1/8 corner

79 78 The 1/4 Sec corner bet Sec 5 & 6

1  
The corner to Sec 5 = 6 = 7 & 8 -

Thence S 1° 7' W bet Sec 7 & 8 var 40° E

40 50 Intersect 166 lks west of 1/4 Sec corner bet Sec 7 & 8

Thence N 7° 16' W on True line bet Sec 7 & 8

20 25 Set Post for 1/8 corner

10 10 10 10 10 10 10 10 10 10