

# RECORD OF SURVEY

No 176

Township 1 South Range 38 East Union County, Oregon.

CHAINS. LKS.

For H L Johnston Done Oct 30<sup>th</sup> 1893

Commenced at the corner to Sec 9-10-15-16 and run west on a line Var 19° E

40 50 Intersected 1/4 sec corner Thence West

81 00 Intersected Sec corner to NW corner of Sec 16

From the NW corner of Sec 16 South Var 19° E

40 50 Intersected 1/4 sec corner on west side of Sec 16 Thence N on true line Var 19° E

20 25 Set Post for 1/8 corner at the NW corner of the SW 1/4 of NW 1/4 Sec 16 from which

A Fir Tree 24<sup>in</sup> in Diameter bears N 8° West Distance 21 lks

From the 1/4 sec corner on the west side of Sec 16 East Var 19° E

40 00 Set Temporary Post for centre of Sec Thence East

81 00 Intersected 1/4 sec corner between Secs 15-16 Thence West on true line

40 50 Set Post for centre of Sec 16 from which

A Pine Tree 18<sup>in</sup> in Diameter bears N 77° 30' East Distance 96 lks

A Pine Tree 36<sup>in</sup> in Diameter bears S 74° 30' West Distance 54 lks

From the 1/4 sec corner between Secs 9-16 South Var 19° East

40 50 Intersect centre of Sec 16 20 lks West of Post Thence N on true line Var 19° 12'

20 25 Set Post for the NE corner of SE 1/4 of NW 1/4 of Sec 16

J L Curtis  
County Surveyor  
by Arthur M A Curtis  
Deputy

