

RECORD OF SURVEY

No 178

Township 4 South Range 41 East Union County, Oregon.

CHAINS. LES.

For G D Johnson Done March 26th 1894

This survey was made to establish the East and west line through the centre of Sec 18.

I commenced at the 1/4 Sec corner on the West Boundary of Sec 18 and offset 2 Chs to the South thence East

| | | | |
|-----------|--------------|-----------|-----------|
| | | | |
| | | | |
| 21.25 chs | 19.77 Sec 18 | 19.77 chs | 19.77 chs |
| | | | |
| | | | |

7 00 Offset back North 2 Chas and then East

14 25 Set Temporary Stake for 1/16 corner to SE corner of SW 1/4 of NW 1/4 Sec 18 thence East

20 00 Set temporary Stake for centre of Sec thence East

20 00 " " " " 1/16 corner " "

19 31 Intersected the 1/4 Sec corner between Secs 17 & 18 45 Chs south of the corner from the 1/4 East on true line

19 71 Set 1/16 corner -

39 54 Set Stake for centre of Sec

59 31 Set corner for SE corner of SW 1/4 of NW 1/4 Sec 18

80 56 Intersect the 1/4 Sec corner on West Bdy of Sec 18

J L Curtis
County Surveyor