

Township 9 South Range 45 and 46 E. W. Union County, Oregon.

CHAINS.	LKS.	Oct. 24-1899						
				20.04	20.00	20.	20.14	20.13
				20.07	20.07			20.14
				E. Sullivan				Evans
				20.		Hartley		
				20.07				20.13
				Graham				
		25		20.			30	
								20.13
								20.13
								19.87
								19.87

I commenced at the N. W. Cor. Sec. 30 and run South Var. 19° 40' E
 20 Set Temp. Cor.
 40 14 The 1/4 Sec. Cor. from which a cottonwood tree bears South 80° E. 60.0k. distance
 Then I run North on line
 20 07 Set 1/8 Sec Cor. a Rock 14-12-8" Then I run west from N.E. Cor. 25
 20 Set Temp. "
 80 16 The N. W. Cor. Sec. 25 Thence from Cor. East
 60 12 Set a rock 16-6-6 for 1/8 Sec. Cor. Thence South from 1/8 Cor
 20 07 Set Temp. Cor. Then I run from 1/8 Sec. Cor. on East side of Sec. 25
 20 00 Intersected line running N. S. at Cor. Set a stone 16 x 8 x 3 for 1/16 Cor.
 Thence South from 1/16 Cor
 20 07 Set Temp. Cor. Then from 1/4 Sec. Cor. between 25-30 west
 20 00 Set a stone 18 x 10 x 4 for Cor.

G. W. Evans Oct 25- I commenced at the N. W. Cor.
 Sec. 30 and run East Var. 19° 30' East
 40 00 To 1/4 Sec Cor.
 60 00 Set Temp. "
 80 30 The N. E. Cor. Sec. 30 Thence West
 20 15 Set 1/8 Sec. Cor. " South
 20 00 " Temp. "
 40 00 " " "
 80 60 The 1/4 Sec. Cor. on South side Sec. 30. Thence North from 1/4 Cor
 40 30 Set 1/16 Cor. Stone 12 x 8 x 6
 60 45 " " " " 16 x 6 x 4