

1902

193  
210

Township

4 South

Range

39 East

Union County, Oregon.

CHAINS.

LKS.

Turner Oliver June 10-1902

Commencing at the North East Cor. of Sec. 24 T. 4 S. R. 39 E

Thence West Var. 20° E

40 00

No 1/4 Sec. Cor.

80 00

No " "

120 00

" 1/4 " "

160 50

The Sec Cor. of Sec 22+23-14-15-

Then back on true line I set stake at equal distances for center

N. E. 1/4 Sec 23 and the N. W. Cor Sec. 24 Then South from

Sec. Cor.

40 00

Set temp Cor.

80 00

to Sec Line

Then from South East Cor. Sec 24 East West

80 66

No Sec. Cor.

100 83

Set stake for temp 1/8 Cor.

160 36

Found S.W. Cor. Sec 23 Rock in mound of Rock. Then from 1/8 Cor

set by me I run North

40 10

set temp 1/16 Cor.

80 20

The 1/8 Sec. Cor on North line of Sec 23

Then from 1/4 Sec. Cor. on East line of Sec 23 as set by me I sighted  
to the 1/4 Sec Cor. on West line of Sec 23 and at the Intersection  
of line on 1/8 line that I run North I set 1/16 Sec. Cor. just in  
mound of Rocks the S.W. Cor. of N. E 1/4 of the N. E 1/4 Sec 23  
T. 4 S. R. 39 E. W. M.

Arthur Curtis  
County Surveyor