

1902

RECORD OF SURVEY

195
213

Township 1 South

Range 38 East W. M.

Union County, Oregon.

CHAINS.

LKS.

Jake Emd et. al. Dec. 14-1902 Sec. 21-22

Commencing at the South East Corner of Section 21 and run West

20 00 I set temp Cor.

40 00

80 00 the South West Cor. of Sec. 21 then West from N.E. Cor Sec 21

20 00 Set stake

40 00

60 00

80 00 The N. W. Cor Sec, 21 Then South

40 00 The 1/4 Sec. Cor. a stake. Then East

20 00 Set Temp Cor

40 00

60 00

80 25 The 1/4 Sec. Cor. Then I went West on true line and set Cor. stakes at pro ratio of distances. Then from S.E. Cor Sec 16 I run North

20 00 Set temp. Cor

40 40 The 1/4 Sec. Cor. then South on true line

20 20 Set 1/8 Sec. Cor. stake with mound of earth

Then from 1/4 Sec. Cor, on East line of Sec 21 I run East

20 00 Set temp Cor

40 00

60 00

80 64 To 1/4 Sec. Cor. Then I went back and set Cor at pro ratio above stakes and made mounds; then I commenced at the S. E. Cor. Sec. 22 and run North

40 40 the 1/4 Sec Cor

60 20 set 1/8 Sec. Cor.

80 80 the North East Cor. Sec 22

Arthur Curtis
County Surveyor