

Township

Range

Union County, Oregon.

From the center of said Sec. 4, thus established, I ran south on the N+S Center line 1316 feet, being $\frac{1}{2}$ the distance to the south line of said section 4, at which point I established the S.W. Cor. of the NW $\frac{1}{4}$ of the SE $\frac{1}{4}$ of said Section 4.

From this point, after determining the true N+S. line by means of an observation on Polaris, I ran N. $0^{\circ}15'E$. 1900' thence N $59^{\circ}03'E$ 312', thence East, 1036.04' ^(SW Cor. NW $\frac{1}{4}$ SE $\frac{1}{4}$) also from the above mentioned point, I ran East 1303.04'. Iron pins or pipes 3' long and $\frac{1}{2}$ " in diam were set at each cor. established.

Chaimmen: - V. B. Papert and J. O. Shanks
Those present at various times during survey were, A. P. Davis, J. A. Hills, James Simmland, Courtney, Huffman, Riddle, Mulholland and others

Description of corners
N.W. Cor Sec. 4, Post witnessed by Riddle
NW $\frac{1}{4}$ Cor " " " " " "
NE " " " Stone under fence, across lane from Courtney house
S W " " " in Co. Road
S E " " " " " "
E $\frac{1}{4}$ " " " at fence corner, witness by Mulholland.
S $\frac{1}{8}$ Cor of SE $\frac{1}{4}$ " " in Co. Road

Other corners used in survey were established as above described.

The Survey is correctly shown on the accompanying Plat.

Recorded March 29th 1915
J. Mulholland,
Co. Surveyor